

PROJECT ADDRESS:
2180 AMERICAN LEGION
BOULEVARD,
MOUNTAIN HOME, ID 83647

OWNER:
SHELLEY ESSL, COUNTY CLERK
ELMORE COUNTY
150 SOUTH 4TH EAST, SUITE 3
MOUNTAIN HOME, IDAHO 83647



SEEPAGE BED SCHEDULE						
SEEPAGE BED	LENGTH (FT)	WIDTH (FT)	DEPTH (FT)	INFILTRATION RATE (IN/HR)	SOILS	VOLUME PROVIDED (CU FT)
NORTH	100	20	5	0.5	POORLY GRADED SAND	4000
MIDDLE	200	10	5	0.5	POORLY GRADED SAND	4000
SOUTH	100	20	5	0.5	POORLY GRADED SAND	4000

REVISIONS

E	08/27/2026	ADDENDUM #4
D	11/05/2025	PREAPPLICATION COMMENTS
C	09/05/2025	50% CD / OWNER REVIEW SET
B	08/01/2025	100% DESIGN DEVELOPMENT
A	07/03/2025	50% DESIGN DEVELOPMENT
MARK	DATE	DESCRIPTION

ISSUE INFORMATION

PROJECT NO.: **US0043131.4394**
WSP PRINCIPAL IN CHARGE: **KRISJAN HINER**
WSP PROJECT MANAGER: **RICHARD SERVOS**
OWNER APPROVAL:

SHEET TITLE

**STORM DRAINAGE
DETAILS**

SHEET NO.

C3-03

PERMIT SET